



# **AOS Semiconductor Product Reliability Report**

**AO4404B/AO4404BL, rev A**

**Plastic Encapsulated Device**

**ALPHA & OMEGA Semiconductor, Inc**

**495 Mercury Drive  
Sunnyvale, CA 94085  
U.S.**

**Tel: (408) 830-9742**

**[www.aosmd.com](http://www.aosmd.com)**

**Sep 25, 2007**

This AOS product reliability report summarizes the qualification result for AO4404B. Accelerated environmental tests are performed on a specific sample size, and then followed by electrical test at end point. Review of final electrical test result confirms that AO4404B passes AOS quality and reliability requirements. The released product will be categorized by the process family and be monitored on a quarterly basis for continuously improving the product quality.

### Table of Contents:

- I. Product Description
- II. Package and Die information
- III. Environmental Stress Test Summary and Result
- IV. Reliability Evaluation
- V. Quality Assurance Information

### I. Product Description:

The AO4404B uses advanced trench technology to provide excellent  $R_{DS(ON)}$ , low gate charge and operation with gate voltages as low as 2.5V. This device is suitable for use as a load switch or in PWM applications. The source leads are separated to allow a Kelvin connection to the source, which may be used to bypass the source inductance. Standard Product AO4404B is Pb-free (meets ROHS & Sony 259 specifications).

Absolute Maximum Ratings $T_A=25^\circ\text{C}$ unless otherwise noted			
Parameter	Symbol	Maximum	Units
Drain-Source Voltage	$V_{DS}$	30	V
Gate-Source Voltage	$V_{GS}$	$\pm 12$	V
Continuous Drain Current	$T_A=25^\circ\text{C}$	8.5	A
	$T_A=70^\circ\text{C}$	7.1	
Pulsed Drain Current	$I_{DM}$	60	
Power Dissipation	$T_A=25^\circ\text{C}$	2.8	W
	$T_A=70^\circ\text{C}$	1.8	
Junction and Storage Temperature Range	$T_J, T_{STG}$	-55 to 150	$^\circ\text{C}$

Thermal Characteristics				
Parameter	Symbol	Typ	Max	Units
Maximum Junction-to-Ambient	$R_{\theta JA}$	37	45	$^\circ\text{C/W}$
Maximum Junction-to-Ambient				
Maximum Junction-to-Lead	$R_{\theta JL}$	26	36	$^\circ\text{C/W}$

## II. Die / Package Information:

	<b>AO4404B</b>	<b>AO4404BL (Green Compound)</b>
<b>Process</b>	Standard sub-micron Low voltage N channel process	Standard sub-micron Low voltage N channel process
<b>Package Type</b>	8 leads SOIC	8 leads SOIC
<b>Lead Frame</b>	Copper with Ag spot	Copper with Ag spot
<b>Die Attach</b>	Ag epoxy	Ag epoxy
<b>Bond wire</b>	S: Cu 2mils; G: Au 1.3mils	S: Cu 2mils; G: Au 1.3mils
<b>Mold Material</b>	Epoxy resin with silica filler	Epoxy resin with silica filler
<b>Filler % (Spherical/Flake)</b>	90/10	100/0
<b>Flammability Rating</b>	UL-94 V-0	UL-94 V-0
<b>Backside Metallization</b>	Ti / Ni / Ag	Ti / Ni / Ag
<b>Moisture Level</b>	Up to Level 1 *	Up to Level 1 *

**Note \*** based on info provided by assembler and mold compound supplier

## III. Result of Reliability Stress for AO4404B (Standard) & AO4404BL (Green)

Test Item	Test Condition	Time Point	Lot Attribution	Total Sample size	Number of Failures
Solder Reflow Precondition	Standard: 1hr PCT+3 cycle reflow@260°c Green: 168hr 85°c /85%RH+3 cycle reflow@260°c	0hr	Standard: 7 lots	770 pcs	0
HTGB	Temp = 150°c , Vgs=100% of Vgsmax	168 / 500 hrs 1000 hrs	2 lots  (Note A*)	168 pcs  77+5 pcs / lot	0
HTRB	Temp = 150°c , Vds=80% of Vdsmax	168 / 500 hrs 1000 hrs	2 lots  (Note A*)	168 pcs  77+5 pcs / lot	0
HAST	130 +/- 2°c , 85%RH, 33.3 psi, Vgs = 80% of Vgs max	100 hrs	Standard: 3 lots  (Note B**)	165 pcs  50+5 pcs / lot	0
Pressure Pot	121°c , 29.7psi, RH=100%	96 hrs	Standard: 4 lots  (Note B**)	220 pcs  50+5 pcs / lot	0
Temperature Cycle	-65°c to 150°c , air to air,	250 / 500 cycles	Standard: 7 lots  (Note B**)	385 pcs  50+5 pcs / lot	0

### III. Result of Reliability Stress for AO4404B (Standard) & AO4404BL (Green) Continues

DPA	Internal Vision Cross-section X-ray	NA	5 5 5	5 5 5	0
CSAM		NA	5	5	0
Bond Integrity	Room Temp 150°c bake 150°c bake	0hr 250hr 500hr	40 40 40	40 wires 40 wires 40 wires	0
Solderability	245°c	5 sec	15	15 leads	0
Die shear	150°c	0hr	10	10	0

**Note A:** The HTGB and HTRB reliability data presents total of available AO4404B and AO4404BL burn-in data up to the published date.

**Note B:** The pressure pot, temperature cycle and HAST reliability data for AO4404B and AO4404BL comes from the AOS generic package qualification data.

### IV. Reliability Evaluation

**FIT rate (per billion): 64**

**MTTF = 1783 years**

In general, 500 hrs of HTGB, 150 deg C accelerated stress testing is equivalent to 15 years of lifetime at 55 deg C operating conditions (by applying the Arrhenius equation with an activation energy of 0.7eV and 60% of upper confidence level on the failure rate calculation). AOS reliability group also routinely monitors the product reliability up to 1000 hr at and performs the necessary failure analysis on the units failed for reliability test(s). The presentation of FIT rate for the individual product reliability is restricted by the actual burn-in sample size of the selected product (AO4404B). Failure Rate Determination is based on JEDEC Standard JESD 85. FIT means one failure per billion hours.

$$\text{Failure Rate} = \text{Chi}^2 \times 10^9 / [2 (N) (H) (Af)] = 1.83 \times 10^9 / [2 (2 \times 164) (168) (258) (258)] = 64$$

$$\text{MTTF} = 10^9 / \text{FIT} = 1.56 \times 10^7 \text{ hrs} = 1783 \text{ years}$$

**Chi<sup>2</sup>** = Chi Squared Distribution, determined by the number of failures and confidence interval

**N** = Total Number of units from HTRB and HTGB tests

**H** = Duration of HTRB/HTGB testing

**Af** = Acceleration Factor from Test to Use Conditions (Ea = 0.7eV and Tuse = 55°C)

$$\text{Acceleration Factor [Af]} = \text{Exp} [Ea / k (1/Tj u - 1/Tj s)]$$

**Acceleration Factor ratio list:**

	55 deg C	70 deg C	85 deg C	100 deg C	115 deg C	130 deg C	150 deg C
<b>Af</b>	<b>258</b>	<b>87</b>	<b>32</b>	<b>13</b>	<b>5.64</b>	<b>2.59</b>	<b>1</b>

**Tj s** = Stressed junction temperature in degree (Kelvin), K = C+273.16

**Tj u** = The use junction temperature in degree (Kelvin), K = C+273.16

**k** = Boltzmann's constant, 8.617164 X 10<sup>-5</sup>eV / K



## V. Quality Assurance Information

Acceptable Quality Level for outgoing inspection: **0.1%** for electrical and visual.

Guaranteed Outgoing Defect Rate: **< 25 ppm**

Quality Sample Plan: conform to **Mil-Std-105D**